EXHIBIT D Off The Rail Timber Sale IDCO2-TS.2025.0001 Road Maintenance Specifications

Page Number	<u>Section</u>
General (2)	3000
Operational Maintenance (3&4)	3100
Seasonal Maintenance (4)	3200
Final Maintenance (5)	3300
Other (5)	3400

GENERAL - 3000

3001 -The Purchaser shall be required to maintain all roads used by him in accordance with Sections 3000, 3100, 3200, 3300, and 3400 of this Exhibit. 3002 -The Purchaser shall maintain the cross section of existing dirt or graveled roads to the existing geometric standards. Any roads required to be constructed, improved, or renovated under terms of this contract shall be maintained to the standards required in Exhibit C of this contract. 3003 -The minimum required maintenance on any roads shall include provisions specified in Subsections 3101, 3104, and 3105 of this exhibit. 3004 -The Purchaser shall be responsible for providing timely maintenance and cleanup on any road(s) with logging units substantially completed prior to moving operations to other roads. Release of maintenance requirements may be granted, upon written request, when the conditions specified in Section 3300 and 3400 are met satisfactorily.

OPERATIONAL MAINTENANCE - 3100

- The Purchaser shall blade and shape the road surface and shoulders with a motor patrol grader. Banks shall not be undercut. Back blading with tractors or similar equipment will be allowed only around landings and other areas when approved by the Authorized Officer.
- The Purchaser shall maintain established berms and place additional berms using adjacent material where needed to protect fills as directed by the Authorized Officer.
- The Purchaser shall perform other road cleanup including removal of debris, fallen timber, bank slough, and slides which can practicably be accomplished by a motor patrol grader, rubber tired front end bucket loader, rubber tired backhoe, or comparable equipment, and by the use of hand tools.
- Removal of bank slough and slide material includes placement at disposal sites where material cannot erode into streams, lakes, or reservoirs or cause undue damage to road fill slopes which have been planted or mulched to control soil erosion.
- The Purchaser shall be responsible for the removal of all slides and sloughs, up to fifteen (15) station yards in quantity, at any one site. This work includes unlimited multiple sites on all roads to be maintained by the Purchaser.

Prior to removal of any slough, or slide material exceeding fifteen (15) station yards at any one site, the Purchaser and the Authorized Officer or their Authorized Representatives shall agree in writing, in the field, to the quantity of material, method of disposal, and the disposal site. Work may commence immediately after agreement.

Upon completion of agreed work, a reduction in timber sale purchase price will be made to offset the cost of the work, based on current BLM Timber Appraisal Production Cost Schedules. Adjustments in purchase price for completed work shall be made as necessary, with no less than once per year when actual work is ongoing.

DEFINITION: ONE STATION YARD IS ONE CUBIC YARD MOVED ONE HUNDRED FEET. EXAMPLE: 15 station yards is 15 c.y. moved 100 feet or 30 c.y. moved 50 feet.

- The Purchaser shall be responsible for maintaining normal flow in drainage structures. This includes cleaning out drainage ditches, catch basins, clearing pipe inverts of sediment and other debris lodged in the barrel of the pipe, and maintaining water dips and water-bars using equipment specified in Subsection 3104 and other culvert leaning and flushing equipment.
- The Purchaser shall cut or trim trees and brush which obstructs vision or prevents the

safe passage of traffic along the traveled way, when directed by the Authorized Officer.

The Purchaser shall also cut trees or brush encroaching on the road prism that are a result of his activities or winter damage during the contract period. Disposal of such vegetation material shall be in accordance with Section 42.H.3. of this contract.

SEASONAL MAINTENANCE - 3200

- The Purchaser shall perform preventive maintenance at the end of Purchaser's hauling each season and during non-hauling periods which occur between other operations on the contract area. This includes cross ditching, removing ruts or other surface irregularities and all other requirements specified in Section 3100.
- The Purchaser shall perform and complete maintenance, specified in Section 3000, 3100, and 3200, on all roads used in conjunction with this contract prior to May 15 of each year, after initial commencement of construction or logging operations. Thereafter all roads shall have continuous preventive maintenance and road cleanup until suspension of seasonal operations. This includes all roads used and not used during the preceding operating seasons.
- The Purchaser shall complete road clean up and maintenance, as specified in Section 3100, at the completion of logging operations on any road(s) located in an area separate from the area where logging activities will resume.
- The Purchaser shall be responsible for performing post storm inspections and maintenance during the spring and fall seasons to minimize erosion and potential road or watershed damage.
- The purchaser shall apply water to the road running surface during extended dry periods when heavy hauling causes excessive dust particulates and surface fine(s) loss to the point of degrading the surface structure of the haul road. Limit water applications to abatement for hauling vehicles and provide at a frequency and rate which controls dust such that vehicle tail lights and turn signals remain visible.

FINAL MAINTENANCE - 3300

The Purchaser shall complete final maintenance and/or damage repairs on all roads used under terms of this contract within thirty (30) days following completion of hauling and in accordance with Section 16(b) of this contract. This work shall include any maintenance and/or damage repairs specified in sections 3000, 3100, and 3200 necessary to meet the conditions specified in subsection 3002 and shall be executed in accordance with subsection 3302 of this section.

The Authorized Officer may grant acceptance of Purchaser's maintenance responsibility in part where certain individual roads or road segments are no longer of any use to the Purchaser's remaining removal operations, provided that all requirements in Sections 3000, 3100, 3200, and 3300 of the maintenance specifications of Exhibit D have been completed and relinquishment of cutting and removal rights on cutting units tributary to these roads is signed by the Purchaser. Request for partial acceptance must be submitted in writing by the Purchaser.

The Purchaser shall perform final road maintenance only when weather or soil moisture conditions are suitable for normal maintenance equipment operations as determined by the Authorized Officer.

If final maintenance is delayed after the date required in subsection 3301 of this contract by adverse soil moisture or unsuitable equipment operating conditions, the Purchaser will be notified by the Authorized Officer when soil moisture and equipment operation conditions are suitable. The Purchaser shall then be required to complete the final maintenance within thirty (30) days.

OTHER MAINTENANCE - 3400

The Purchaser shall be permitted to remove ice and snow from roads authorized for use under this contract only when prior written approval has been secured from the Authorized Officer. The Purchaser shall submit a written request for permission to remove ice and snow in advance of the date operations are to begin.

Upon receiving written authorization for snow and ice removal, the Purchaser will perform the work according to the conditions and equipment requirements set forth in the authorization.